SUBCONTRACTOR PRE-QUALIFICATION & ROUGH-IN SPEC SHEET

# NAVA'S SPRAY FOAM INSULATION LLC

Licensed Arizona Spray Foam Subcontractor · Bilingual Crew (EN / ES) · West Phoenix & Maricopa County

(602) 760-8807
navassprayfoam@gmail.com
https://navassprayfoam.com

| STATE LICENSE | QUALIFYING PARTY | BOND & RECORD | SERVICE COVERAGE |
|---|---|---|---|
| **AZ ROC #368629**<br>Specialty Dual CR-40 (C-40 Comm. + R-40 Res.) | **Bryan Nava**<br>AZCC Entity #23641311 · Family-Owned LLC | **$6,750 Bond #LSM5164280**<br>RLI Insurance Co. · 0 Open ROC Complaints · Exp. 2028-10-31 | **Greater Phoenix**<br>Phoenix, West Valley, Scottsdale, East Valley |

## 01 // FOAM CHEMISTRY & BUILDING CODE BASIS

### 100% In-House Open-Cell Spray Foam

**Core In-House Product:** Breathable Interior Open-Cell Spray Foam (~R-3.7 per inch), formulated for hot desert attics and exterior wood framing.

**Unvented Attic Deck Target (IRC R806.5):** ~10.5 in depth achieves R-38.9 under pitched roof decking, bringing AC ducts and air handlers inside the conditioned envelope.

**Wall Cavities (2×4 & 2×6):** Full continuous air-seal fill (3.5 in = ~R-13.0; 5.5 in = ~R-20.4) with strong sound dampening and zero fiber settling.

**Leak Transparency:** Breathable open-cell lets roof framing dry inward so leaks remain easier to spot rather than hiding moisture behind a vapor barrier.

**Independent Partner Closed-Cell Option:** If architectural or commercial drawings strictly specify interior Closed-Cell (~R-6.5/in), an independent AZ ROC-licensed partner contractor handles that scope, and their license, bond, insurance, and warranty terms appear on their own documents.

## 02 // TRADE SCHEDULING & JOBSITE PREP

### Built for Foremen, Builders & 1-20+ Lots

**Fast Rough-In Turnaround:** Ready right after electrical, plumbing, and HVAC rough-in inspections so drywall crews stay on schedule.

**Full Poly Masking on Open Builds:** Windows, exterior door frames, panels, and concrete slabs are taped cleanly with poly sheeting before spraying.

**Flush Stud Trimming:** Cured wall foam is shaved flat to 2×4 and 2×6 studs prior to drywall hanging; bagged trim scrap hauled off site.

**Lived-In Remodels & Attic Redos:** Direct crew access straight through existing garage or hallway attic openings without taping plastic over occupied rooms.

**Field QC Check:** Handheld infrared thermometer spot checks across exterior wall bays and roof decking prior to wrap-up.

| ASSEMBLY / PROJECT TYPE | RECOMMENDED SYSTEM | DEPTH & PERFORMANCE | DELIVERABLES FOR NEXT TRADE |
|---|---|---|---|
| **New Construction Custom & Multi-Home Tracts (1-20+ Lots)** | Under Roof Deck + 2×4/2×6 Exterior Walls (Open-Cell) | ~10.5" Deck (R-38.9)<br>3.5"-5.5" Studs | Poly-masked windows & slabs, top-plate & boot sealing, studs shaved flush for drywall |
| **Commercial TI, Warehouses & Steel Workshops** | Interior Decking & Wall Cavities (Dual CR-40 Cleared) | Custom Depth per Spec (Open-Cell / Partner CC) | Commercial license + $6,750 bond verification; interior thermal and acoustic barrier |
| **Existing Home Remodels, Additions & Casitas (ADUs)** | Old Insulation Removal + Under-Roof Open-Cell | ~10.5" Deck (IRC R806.5) | Bagged old cellulose removal via attic opening; AC ducts kept cool without living-area taping |

DIRECT BUILDER & ARCHITECT DESK

### Skip Web Forms: Call or Email PDF Plans for Fast Takeoffs

We know superintendents, site foremen, and architects do not fill out homeowner sq-ft widgets. Call direct in English or Spanish or email blueprints for lot pricing and schedule locks.

**CALL / WHATSAPP:** (602) 760-8807
**EMAIL PLANS (PDF):** navassprayfoam@gmail.com
**ROC VERIFY:** azroc.my.site.com (#368629)

**License Scope Notice (A.R.S. § 32-1124):** NAVA'S SPRAY FOAM INSULATION LLC performs interior open-cell spray foam insulation, old blown insulation removal, and handheld infrared spot-temperature checks across Maricopa County under Active Specialty Dual CR-40 License #368629 ($6,750 RLI bond #LSM5164280, 0 open complaints on AZ ROC public record). It is not a CR-42 roofing contractor, HVAC or general contractor, or certified energy auditor, and exterior polyurethane foam roofing or roof coatings are excluded. Independent partner closed-cell work appears on the partner's own license, insurance, and contract documents. Certificate of Insurance (COI) and IRC R316 thermal/ignition barrier requirements depend on project specifications.